

ISSUED TO M/S _____

TENDER DOCUMENT

FOR

**FURNISHING OF
INDIAN OVERSEAS BANK**

AT

CHAMBA (H.P.)

**OFFICE OF THE
CHIEF REGIONAL MANAGER
INDIAN OVERSEAS BANK, RO
SECTOR 7, CHANDIGARH**

ARCHITECTS :

GURDEV GROUP OF ARCHITECTS

SCO 1094-95, SECTOR 22-B,

CHANDIGARH – 160 022

PHONE : 0172-5068450

MOBILE : 094170-08450

Last Date of submission of tenders: 29.05.2026 up to 05:00 p.m.

Date of opening of tenders: 29.05.2026

TENDER FOR THE FURNISHING OF INDIAN OVERSEAS BANK AT CHAMBA

DETAILS OF TENDER

1. Details of work to be done : Interior furnishing and electrical works.
2. Form of Contract : Item wise rate.
3. Earnest Money : Rs. 33,394/- (Thirty-three thousand) Three hundred ninety-four only) in form of Demand draft in favour of Indian Overseas Bank payable at Chandigarh.
4. Period of contract / time of Completion : 25 days
5. Liquidated damages for non-completion of work in time : 5% of the contract value per week subject to a max of 30% of the contract value.
6. Defect Liability Period : 12 months (Twelve months) from the date of virtual completion as certified by Architect / employer.
7. Retention amount for 12 months: 8% of the total bill.
8. Period of submitting of Final bill. : 15 days from the date of completion.
9. Mobilisation Advance / Secured Advance : No. Mobilization Advance / secured Advance will be given to the Contractor.

TENDER FOR THE FURNISHING OF INDIAN OVERSEAS BANK AT CHAMBA

GENERAL CONDITIONS

1. The Contractor shall sign each page of this tender.
2. Payment to the Contractor Agency shall be made as per actual work done at site.
3. Quantity of work may increase or decrease at site as per requirement, which shall not affect the rates quoted by the contractor.
4. Furnishing works including electrical works etc. shall be done to the complete satisfaction of Bank and Architect-in-charge.
5. All teak / Cedar wood / rubber wood to be used should be knotless which is to be polished with all background surface preparation coarses maintaining the visibility of wood grains.
6. The contractor agency shall keep particular vigil on his workers / carpenters / painters etc. to maintain very good workmanship of all items, failing which no payment shall be made and no claim of material / labour used shall be made to him in any case, and the same work shall be executed by him again without charging any extra cost.
7. All rates shall be quoted in words & figures & any cutting over writing shall be signed.
8. All items to be executed, as per drawings, if any change is required, the same shall be brought to the notice of Architect-in-Charge.
9. Any addition, alteration or correction shall be signed and stamped properly.
10. Contractor agencies are advised (before quoting the rates) to inspect the site of the proposed work. He must go through all drawings and specifications and documents.
11. The Bank reserves the right to accept / reject any tender / quotation without assigning any reason.
12. The Contractor agency should have already executed works of furnishing interiors & exterior, civil works of very good workmanship.
13. Quality of material and workmanship rejected by the Architect / Concerned Authorities shall be removed immediately by the contractor and rectified / replaced.
14. No advance payment or any part payment shall be made to the Contractor. Only final payment shall be made on completion of all works mentioned in the tender.
15. The rates shall include the cost of coat of anti-termite treatment on all wooden frame work and all commercial ply / board used for partitions and paneling, furniture etc. The contractor/s shall have to dismantle & dispose the existing counters, tables, partitions, electrical items etc. within the quoted cost of the total furnishing works.

16. Rates for partitions, paneling, wall cladding and false ceiling shall include cutting and making good of necessary cut-outs/chiseling to be made for electrical conduits, switch boards etc.
17. Bank shall not be responsible for any loss or damage to the contractor/labour due to any natural calamity during the course of construction. Contractor is liable to make good all the damages if any, till the work is completed and handed over to the Bank authorities.
18. Unless, otherwise mentioned all materials to be used shall be I.S.I. marked. Failure to do so, the work may be rejected and in that case contractor shall have to remove the defective materials and replace / re-do the work for which no claim shall be entertained.
19. The total work shall be supervised by the Architect-in-Charge and he/she shall be kept fully informed by the contractor regarding the progress of work.
20. Bank may award the work in part or whole to a single party or any other party.
21. It may please be noted that the Bank is not bound to allot the work to the lowest party. And as such, the allotment of work shall be based on workability of rates quoted by the contractor on account of quality work.
22. The bank reserves the right to reject any or all the tenders without assigning any reason whatsoever.
23. The earnest money deposited shall not carry any interest and will be refunded to the unsuccessful tenderers.
24. Earnest money paid by the contractor shall be forfeited by the Bank if contractor fails to undertake the job if he is communicated about acceptance his rates/tender.
25. The contractor shall take all the necessary precautions while working and to safe guard adjacent property, Bank's property, Bank's Employees, and traffic persons.
26. All the rates quoted are inclusive of removal of rubbish/ debris collected during the progress of work, rejected materials etc.
27. The contractor shall not directly or indirectly sublet the work to other party without written permission of the Bank.
28. The quantities mentioned in schedule are provisional and likely to increase/decrease to any extent or may be omitted thus altering the aggregate value of the contract. No claim for loss of profit / business shall be entertained on this account.
29. The Bank reserves the right to distribute the work for which quotations have been called, among more than one parties, if found necessary. No claim in this respect shall be considered and the contractor agrees to cooperate with other agencies appointed by the Bank.
30. All the workers of the contractor must be properly covered by an insurance policy under "Workman's Compensation act" and "Fatal Accidents Act". The contractor at his own expenses arrange to effect and maintain until the virtual completion of the contract, insurance policy in the joint name of Bank and the contractor against this risk to be retained by the Bank until the virtual completion of the work, and indemnify the Bank from all the liabilities arising out of such events. In case of delay, contractor shall arrange to extend insurance policy till work is completed.

31. All the work should be completed within the specified period in the tender. If the work is delayed due to the reasons beyond the control of the contractor, he should keep intimating the Bank explaining, therein the reasons for such delays, immediately and if in the opinion Bank's authorities the delay is justified, the contractor shall be granted extension in time limit.
32. The contractor shall furnish well in time before work commence at his own cost, colour samples, samples of materials or workmanship that may be called by Bank's Architect / Engineer for approval. Rates quoted shall cover for such preliminary work.
33. All the glass panes, door handles/ hinges, electric fittings, fans, furniture, records, floors etc. are to be thoroughly cleaned after the work is completed.
34. The rates quoted by the contractor shall be firm throughout the duration of contract (including extension of time if any granted) and will not be subject to any fluctuation due to variation in cost of material and labour.
37. Conditional tenders are liable to be rejected.
38. The successful tenderer is bound to carry out any item of work necessary for the completion of the job even those such items are not included in schedule of quantities.
39. If in any case of work required to be abandoned, the contractor shall not be entitled for any claims and he will be paid as per the actual work done till that period.
40. Decision of the Bank shall be final and binding on any matter connected with the work. The matter of any dispute shall be decided after mutual discussions based on the terms and conditions of this contract. However, if the matter can not be resolved then the same shall be referred to the respected qualified person in agreed to both the parties and his opinion shall be binding on both the parties. However, this is precourse to any legal action in this regard.
41. If at any stage during the progress of work, it is observed that the contractor is not progressing the work with due diligence, care of lagging much behind the schedule or fails to gear up the work despite instructions from Bank's Architect, the Employer (Bank) reserves the right to terminate the contract with 7 days notice. In such case the contractor shall be liable to pay the Employer to pay any extra cost involved for the completion of the said work and will not obstruct any way in completing the work through other agency. After completion of entire work the contractor shall be paid for the actual work executed by him at the quoted rates after deducting any claims, damages. In case of such termination the security deposit held by the Bank will be forfeited.
42. Contractor shall follow all rules / regulations in force and should posses the license for employing labour and also follow all safety measures, labour bye laws and shall be responsible for any lapse.
43. At any stage i.e. during the execution of work, any kind of change reqd. whether it is in design or specification the same has to be in-corporated by the contractor.

CONTRACTOR

INDIAN OVERSEAS BANK

TENDER FOR THE FURNISHING OF INDIAN OVERSEAS BANK AT CHAMBA

SPECIFICATIONS / BRANDS / MAKE OF ITEMS TO BE USED.

<u>DESCRIPTION</u>	<u>BRAND</u>
a) Board / Ply / ACP :	ARCHID, Green Ply, Duro, ALSTRONG ISI Marked
b) Laminate 1mm th. :	Merino, Formica, Greenlam, Century, AICA
c) Door Closer / Floor spring :	Everite, Doorking, Sandhu ISI Marked.
d) Drawer & Keyboard, Slide Rails :	Earl Bihari, Ebco
e) Glue for fixing commercial Board / Laminate :	Fevicol (Pidilite)
f) Glass :	Triveni, Modi Float
g) Mortice Latch & Lock :	Godrej, Harrison
h) Vertical Blinds :	Vista Levelor / Mac.
i) Tapestry/leather foam :	Harmony, Vimal, Bhor
j) Aluminium Sections :	Jindal/Mahavir/Hindalco
k) False Ceiling :	Gypsum marked "Gypsteel"
l) Synthetic Enamel :	Asian, Nerolac, ICI, Berger
m) Emulsion Paint/Plastic Paint :	Asian, Nerolac, ICI, Berger
n) MCBs :	Havells, L&T, Legrand
o) DB's :	Havells, L&T, Legrand
p) Switch & Socket (Modular) :	Havells, L&T, Legrand Anchor Roma
q) Pipe (PVC) :	Uniplast, D-Plast, AKG
r) Telephone Cable :	Delton
s) Wires :	Havells, Finolex, R.R. Kabels
t) Cables :	Grandley, ICC, R.R. Kabels.
u) Fans :	Khaitan, Crompton, Orient
v) LED's light fittings :	Crompton, Philips, Wipro
w) Amp / Voltage Meters :	Meco / Vasd / Rotomatic or Eq.

CONTRACTOR

INDIAN OVERSEAS BANK

TENDER FOR THE FURNISHING OF INDIAN OVERSEAS BANK AT CHAMBA					
S No	DESCRIPTION	QTY	UNIT	RATE	AMT
1(i)	Providing & Fixing false ceiling at 9'-0" ht. (as per drg.) of India Gypsum Ltd. (GMFSC-4.1) using 12.5mm thick Gypboard, paper tape, jointing compound, G.I. Sections marked "Gypsteel" to be placed at 4'-0" C/C in one direction and at 1'-6" C/C in other direction. The false ceiling shall be finished properly after cutting / making holes for fixing light fixtures including three coats of oil bound distemper paint etc. complete as per drgs.	560	Sqft.		
iii	PPGI METAL SHEET FALSE CEILING: Providing & fixing in position false ceiling in Armstrong 600 x 600 mm PPGI Metal microlook lay-in standard perforated tiles silhouette 38 made of 120 gsm pre-painted galvanised iron, Grade-GPL as per IS277 (2018) with coating durability as per IS 4246 color as approved by Bank/architect with 15mm exposed grid system (Grid frame shall have black groove at bottom) by Armstrong Co. with suspenders. Making necessary framework for A.C. ducting, if any, and necessary cutouts for diffusers and light fittings, taping and finishing to proper line & level, including making grooves and trap doors for A.C unit.	380	Sqft.		
2 i	TOUGHENED GLASS DOORS & PARTITION (for entry: Bank & ATM and Manager Cabin): Providing & fixing 12 MM thick toughened glass for door and fixed glazing, with complete patch fittings such as handles, lock and L-brackets etc. The job shall also include etching design.	220	Sqft.		
ii	P/F floor spring for toughened glass doors.	3	Nos		
3	Providing and fixing wooden partition made of internal frame of alum sections of size 1.75"x1.75" placed at 2'-0" c/c vertically and horizontally finished with 9mm thick commercial ply on both sides with 1.00 mm thick laminate on both sides with horizontal grooves. These partitions shall have 5.00 mm thick glass (etching as per design) above 2'-6" ht. or 4'-0" ht with beading 1/2"x1 1/2" . The rate of partition shall include providing & fixing wooden door finished with laminate on both sides and partly glass, but with complete hardware required such as latches, stopper. The low ht. partition shall have rubber-wood / teak-wood gola of size 3" x 3/4" which shall be polished as per shade reqd.	0			
3(i)	Low ht. partitions with 12 mm thick glass.	80	Sqft.		
(ii)	Full ht. partitions with 5 mm thick glass.	250	Sqft.		
(iii)	a) Cash-Cabin's pts (7'-3" high)	60	Sqft.		
(iv)	b) Cash cabins' as well as single windows' front ptn. with 12mm th. Glass.	30	Sqft.		
(v)	Partition in strong room.	72	Sqft.		
(vi)	Rear partition.	30	Sqft.		
(vii)	Cost Mortice locks (with handles)	4	No		
(viii)	Cost of Multipurpose locks for storages, drawers etc.	25	No		
(ix)	Cost door closers.	4	No		
(x)	Cost floor springs.	0	No		
(xi)	Cost of Knight Latches	1	No		
4(i)	P/F wall paneling on alum section frame 1" x 2" placed @ 2'-0" c/c horizontally & vertically @ 1'-0" C/C, finished with 9mm thick commercial ply by making horizontal grooves of size 3/8"x3/8", 1.00 mm thick laminate as	360	Sqft.		

	per design, the paneling shall be closed with 2" x 1" rubber wood beading				
ii	Making cove in paneling.	0	Rft.		
5(i)	Banking Counters with 1½" thick post-form factory made Tops: Providing & fixing Banking Counters (SW) as per design, 2'-6" ht. & 3'-3" ht. (2 heights). The banking counters shall have the provision to adjust the key board, drawer, storage complete (full length & width) shelf for CPU at bottom and foot rest. The banking counters shall be made of 19mm thick commercial board, with rubber -wood Gola of size 1½ "x ¾ ", which is to be polished as per color scheme. The counter shall be finished externally and internally with 1mm thick laminate of approved shade / colour, handles, magnet catchers, hinges. Inside of drawers, storage cabinet portion shall also be finished with 8mm thick laminate of approved color.	4	Rft.		
6	Tables with 1½" thick post-form factory made Tops: Providing & fixing office tables with/without drawer and storage below of size 2'-4½" (wide), 2'-6" (high) with the provision of key board, with sliding channels of Ebco, complete (full length & width) shelf for CPU at bottom and foot rest. The table shall be made of 19mm thick commercial board; 1mm thick laminate on (inside & outside) with rubber -wood gola of size 1 ½" x ¾ " polish, side golas etc., with hardware such as hinges, catchers and handles. Inside of drawers, storage cabinet portion shall also be finished with 8mm thick laminate of approved color.	18	Rft.		
7	Side Rack with 1½" thick post-form factory made Tops: Providing and fixing side rack, 2'-3" ht. as per design. These racks shall have two drawers with storage below and be made of 19mm thick commercial board; 1mm thick laminate (inside & outside) with rubber -wood gola of size 1 ½" x ¾" polish, side golas, handles, catchers, hinges etc. Inside of drawers, storage cabinet portion shall also be finished with 8mm thick laminate of approved color.	18	Rft.		
8	STORAGE CABINETS: with 1½" thick post-form factory made Tops: Providing and fixing storage cabinets low ht and full ht x 16" (Deep) along the walls/partitions, as per interior drawings, using 19mm board for carcass, shutters, vertical and horizontal partitions, 6mm ply for the back and 1mm High Gloss laminate of approved shade on vertical and horizontal visible surfaces. The shutters shall be overlapped on the carcass and shall be provided with EBCO hinges. The width of the shutter shall be between 12" to 15" as per the site conditions. All the exposed edges of the board shall be provided with wooden lipping 19mm x 3mm, duly PU polished/deco painted in desired shade. The inner surface shall be provided with 0.8mm thick laminate of desired shade, design and gloss. The cabinet shall be complete with handles, knobs, locks and magnet catchers etc. to the satisfaction of the Architect/Engineer.	340	Sqft.		
9	Cash Counters with 1½" thick post-form factory	4.5	Rft.		

	made Providing & Fixing Cash – counters 2'-9" wide, with two levels i.e. 2'-6" & 4'-0" ht. The lower portions top & all other exposed surface shall have 1mm thick laminate (inside & outside) and golas/margins. The lower portion on cashier side there will be provision of 3 nos. drawers with sliding channels of Ebco. for cash, stationery, key board, etc. rubber -wood beadings / gola etc. Inside of drawers, storage cabinet portion shall also be finished with 8mm thick laminate of approved color.				
10	Manager Table with 1½" thick post-form factory made Tops: 7'X3' Providing & fixing Branch Manager table 2'-6" ht. with rubber-wood Gola of size 1 ½" x ¾". as per drgs. having drawer/s, storage cabinet, key board, with sliding channels of Ebco, foot rest, space for CPU & Monitor, all as per drg. / design, the table shall be made with 19mm thick com. Board finished with 1 mm thick laminate (inside & outside) hardware, such as handles, catchers, hinges etc. shall be provided as per requirement. Inside of drawers, storage cabinet portion shall also be finished with 8mm thick laminate of approved color.	6	Rft.		
11	Providing & fixing writing stand of size 3'-0" x 1'-0" x 1'-7 ½" high (face area) as per design drg. Made of 19mm th. Com. Board, 1 mm th. Laminate with rubber wood lipping etc.	3	Rft.		
12(i)	Providing & fixing notice board of size 2'-6"x 4'-0" finished with ivory colour 1mm th. laminate, 1"x1" th. rubber wood beading on all sides.	1	No		
(ii)	Providing & fixing soft boards of size 3'-6"x 2'-0" (covered with openable glass shutters) on 10mm th. comm. ply 12mm th. soft board finished with cotton fabric, 1"x2" rubber wood beading.	1	No		
13	Providing & Fixing cheque drop box and complaint box of size 18" x 27" as per detail.	2	No		
14	Painting work on walls & cemented ceiling in whole premises with oil bound distemper paint and enamel paint on shutters and grills.	0	Sqft.		
15	P/F Zebra blinds of vista / Mac of approved shade / colour.	0	Sqft.		
16	Providing & supplying dressing table with mirror of size 1'-0"x5'-0" including sitting desk for lockers room.	1	No		
17	Providing & supplying wooden planters made of 19mm th commercial board and finished with 1mm th laminate internally and externally.	0	Nos		
18	P/F Glow Sign Board as per approved design, made of 3M vinyl sheet 20'x4'-0" complete with internal tubes 25 Nos. of Crompton make (copper choke) External frame work of G.I. Sheet, 18 gauge, M.S. angle frame / or M.S. square pipes 1 ½" x 1 ½" with outer beading, complete in all respects	90	Sqft.		
19	Providing & fixing in position Aluminium Composite Paneling, partitions & rolling shutter box paneling (ACP) with framing of Aluminium Tube sections of min 1.5" * 1" and 18 gauge 2'-0" C/C both ways. ACP to be in 2' width panels or distributed equally. Panels to be fixed to the frame with 3M or equivalent adhesive. Joints to be finished with Silicon based sealant (Black colour). ACP thickness of 3mm minimum. Aluminium foil thickness to be min 0.20 mm on both sides. Alstrong, ALEX, Alstone, Alcobond, prime bond or equivalent ISO certified or approved brands to be used. Shades to be as per bank's approval. It has to be used for cladding,	450	Sqft.		

	boxing over main door and both side Jam of main door and fixed glazing. Complete panelling should be of ACP.				
20	IOB Providing , making to shape and size (as per the design provided) and fixing to position IOB logo made out of ACP / Acrylic sheet of bank color (pre approved) fixed to position with aluminium framework with required screws, nutts bolts and hooks etc. of size 2' x 2', including outer frame finished with teak wood vinear ply with cove for lighting as LED strip. Below logo, the bank's name shall be written in golden / orange ACP sheet letters as per design.	4	Sqft		
	TOTAL				
2	ELECTRICAL WORKS				
S No	DESCRIPTION	QTY	UNIT		
1 i	Providing & Fixing 2'x2' recessed / or panel model mounted LED Luminaire LCTLR-36-CDL of Crompton.	13	No		
2(i)	Providing & Fixing 15 W LED ROUND DOWNLIGHTER LCND-15-CDL of Crompton.	27	No		
(ii)	Providing & fixing LED tube lights 1x20W of Philips.	10	No		
3(i)	Providing & Fixing Metal wall fans	8	No		
(ii)	Exhaust Fans 12" Dia : 1400 rpm (Double ball bearing) Heavy duty Crompton Greaves / Phillips.	3	No		
(iii)	Providing & Fixing ceiling fans: Khaitan / Crompton Greaves / Orient 4' dia.	2	No		
(iv)	Cost of modular regulators of Havells / Anchor ROMA makes.	2	No		
v	Supply Installation, testing & commissioning of LED STRIP light with driver and Accessories complete as required (MS CROMPTON or equivalent of WIPRO , PHILLIPS, BAJAJ etc. Warm White Cat No. 38389 (M/S Philips)	30	Mtr		
4	ELECTRICAL POINTS : Providing laying, fixing & testing of electrical points including wiring from MCB's to switches, plate type switches, socket & M.S. Modular boxes with rust proof treatment size to accommodate the required nos. of switches & sockets plus circuit wiring from switches to lights/fans/fixtures etc. wherever required complete with earthing 1.00 mm2 multi strand wire in 25mm dia. Unbreakable PVC conduit ISI marked with specials under floor / wall & above false ceiling or making truff under / along work – stations including chase cutting, disposal of melba away from the site and repair of the same with cement mortar, copper conductor wires only will be used of approved make.	0			
a)	Air Conditioning wiring: Supplying & laying of Eletrical flexible cable of 5x2.5sq.mm multi strand suitable for 2.0 Tr , 1.5 Tr & 1.00 Tr H.W Split/Cassette unit between Indoor & Outdoor units shall be considered as ONE length for the purpose of measurement. (Make : Havells/Legrand/ KEI/ Finolex)	5	Nos		

b)	A/C wiring from AC D/B to indoor unit with 5 x 2.5 sq.mm. with one no. 1.5 sq.mm. insulated copper conductor of PVC insulated PVC sheathed armored cable of 1100 V (IS-1554 part I) and fixing of cable on wall with suitable size of clamps/ saddles or laid in floor/recess wall including cutting of floor/wall and making good the damages etc.	5	Nos		
c)	P/F metal clads for A.C.'s: Supplying and fixing 20 A, 240 V, SPN Industrial type socket outlet, with 2 pole and earth, metal enclosed plug top alongwith 20 A "C" curve, SP, MCB, in sheet steel enclosure, on surface or in recess, with chained metal cover for the socket out let and complete with connections, testing and commissioning etc. as required.	5	No		
d)	P/F cable (for UPS room) 16mm 4-core Alum. Cable armoured.	20	Mtr		
e)	15 Amp wiring with 2.5mm sq. multi strand PVC copper wire & metal clad enclosure sockets & plus.	8	No		
f)	5 Amp plug point wiring with 1.5mm sq. multi strand PVC copper wire inc. Plate switches, sockets, plugs. Etc.	30	No		
g)	Call-bell point wiring including Ding-dong bell with 1.5mm sq. multi strand PVC copper wire including plate switches, sockets, etc.	1	No		
h)	Wall Fan points with 3-pin socket and switch, lights & exhaust fan point wiring with 1.5mm sq. from D/B to switches & fittings multi strand PVC copper wire including plate switches, sockets, etc. (For payment no. of switches shall be counted).	65	No		
i)	Signage wiring – P&F of 3x4mm & copper flexible wire & PVC conduiting of ISI make complete with all accessories like Saddles, bends modular switches etc.	1	No		
5	UPS POINTS: P/L & testing electrical three point wiring /circuit wiring having individual circuits for computers with 2.5mm ² Multi-strand copper PVC wire in unbreakable PVC conduits 25mm dia wall thickness 2mm thick with specials under floor / wall & above false ceiling including chase cutting, disposal of malba away from the site and repair of the same with cement mortar, incl. Switches & socket M.S. switch boxes with rust proof treatment size to accommodate the required nos. of Modular switches, sockets etc. & plate type sockets with indicator three in one plate including earthing with 1.00 mm ² multi strand wire complete in all respect.	0			
(i)	Set of 6 amp. 4 sockets & 4 switches	18	SET		
ii	P/F inverter wiring to switch boards.	6	Nos		
6	GEL TYPE CHEMICAL EARTHING (Distance between each pit shall be min 1.5meter) Supplying and installation of copper Gel Earthing station having length 3000 mm including bore-well, chamber with cover and all required civil allied works each earth pit to filled with 2 bags in 30 Kg pack of "Black-Fill Compound" (BFC) EARTHING CONDUCTORS: Wiring with 1x10 sqmm PVC insulated copper conductor wire of 650/1100 volts grade (Finolex make flame guard quality) as earth wire with concealed/exposed PVC pipe including making all the connections.	2	No		
7	Providing and fixing of PVC conduit in wall floor including Telephone wire, M.S. box and two pin telephone sockets or R.J. – 11 plates out let incl. Testing and commissioning etc. as required.	4	No		

8(i)	Providing, laying, testing and commissioning CAT-VI/ Lucent / D-link computer networking cable in PVC conduit in floor or wall from server room to each table with I.O.'s (Socket)	18	No		
(ii)	Supplying of patch chords for computers 1m & 2m length.	8	No		
9	Elect D/B with all internal connections for electrical and generator connections with 10 sq.mm multi strand copper wire, which shall include the following items.				
(i)	Amp Meter and voltmeter set	1	SET		
(ii)	Kit-kats 125 Amp.	3	No		
(iii)	Neutral link.	1	No		
(iv)	Aluminum bus bar 125 Amp proper tinned.	1	No		
(v)	125 Amp. Main switch MCCB type.	1	No		
v	63 Amp. switch MCCB type for AC', Lights D/B's.	0	Nos		
(vi)	Change -over 100 Amp. 3-Phase.	1	No		
(vii)	Providing and fixing different rated MCB,s DP's, for lights, fans, and power supply of Havells make.	24	No		
(viii)	Providing and fixing TPN (tripping type) of 100 Amp of Havells make. (one for lights and one for power supply)	2	No		
ix	Making double-door powder coated M.S. Distribution board 3'x4' to accommodate the above noted electrical items.	12	Sqft		
x	P/F 3 phase 4-way D/B (Quote the cost of Box only)	2	nos		
	UPS SUPPLY				
xi	Providing and fixing (MCB type) DP of 63 Amp of Havells make for UPS supply including 4-way boxes.	8	No		
xii	P/F SP 4-way TPN Boxes for UPS input-output	2	Nos		
xii	Providing and fixing different rated MCB,s for UPS supply of Havells make.	10	No		
xiii	P/F single phase 1 nos 8-way & 1 no. 6-way D/Bs (Quote the cost of Box only) for UPS supply for MCB's: 1 for tables & 1 for Alarms, fire alarm & CCTV .	2	No		
10(i)	Providing & fixing main electrical cable 4- core al. cable armored from elect. pole to meter 35mm dia.	30	Mtr		
(ii)	P/F generator wire/cable 16mm 4-core Alum. Cable armoured.	30	Mtr		
11	Connectivity for the VSAT / leaselines (material & labour) – P&F of 40mm PVC conduit of ISI make including data cable of D-link & RJ-45, complete for connectivity.	1	No		
12	Providing, fixing, testing and commissioning computers 24- Ports networking switch, patch panel & fan with racks	1	No		
13 (i)	P/L copper pipe with complete insulation required for 1.5 ton split type A.C.s from the place of external units upto the location of inside units.	100	Rft		
(ii)	Providing and laying 25mm dia. PVC pipe heavy duty Diplast make for drainage of water of inside units.	80	Rft		
	TOTAL				
3	AIR CONDITIONING				
i	Supply and instalation of 1.5 TR 5-Star High Wall Split AC with cordless remote, of Carrier / Blue Star / Voltas	4	Nos		
ii	Supply and instalation of 1.0 TR 5 Star High Wall Split AC of Carrier / Blue Star / Voltas	0	Nos		
iii	4 KVA Stabilizers	4	Nos		
iv	Out Door unit stand for 1.0/1.5 TR AC.	4	Nos		
	TOTAL				
	SUMMARY				
1	FURNISHING WORKS				
2	ELECTRICAL WORKS				
3	AIR CONDITIONING				
	TOTAL				

	Discount, if any			(-)	
	TOTAL				
	GST 18%				
	Net Total				
Rs. in words.) 					

CONTRACTOR

INDIAN OVERSEAS BANK