

PROPOSED ELECTRICAL WORKS FOR INDIAN OVERSEAS BANK -MATHURANTHAGAM BRANCH					
S.No	Description Of Work	Qty	Unit	Rate	Amount
A	Supply, Installation & Commisioning of the following				
1	MAIN DB(6 WAY VTPN DB)				
	Three Phase, Distribution board with neutral bar, earth bar, cables ties,top and bottom removable gland plate and with necessary adopter boxes if any. The DB should be double door with provisioin of MCB & MCCB etc. as required including cuting of wall and plastering the same with neat finish. It comprising as flolows:-				
	Incomer : 1 X 125 A 3P MCCB, 25Ka				
	Outgoings, 10ka rating:				
	63A TP MCBs - 1No for ACs 40A TP MCBs- 4 Nos for UPS, Ligthing, Rawpower etc	1.00	Set		
2	AC Distribution Boards - 6WAY TPN DB				
	Three Phase, Distribution board with neutral bar, earth bar, cables ties,top and bottom removable gland plate and with necessary adopter boxes if any. The DB should be double door with provisioin of MCB etc. as required including cuting of wall and plastering the same with neat finish. It comprising as follows:-				
	Incomer : 1 X 63A 4P MCB				
	Outgoings:				
	25/32 Amp SP MCBs- 13 Nos	1.00	Set		
3	LIGHTING DB-1nos (12 WAY SPN DB)				
	12 Way SPN Distribution board with neutral bar, earth bar, cables ties,top and bottom removable gland plate and with necessary adopter boxes if any. The DB should be double door with provisioin of MCB etc. as required including cuting of wall and plastering the same with neat finish. It comprising as follows:-				
	Incomer : 40 A 4P MCB				
	Outgoings:				
	16/10A SP MCBs- 9 Nos	1.00	Set		
4	UPS DB (12 WAY SPN DB)				
	12 Way SPN Distribution board with neutral bar, earth bar, cables ties,top and bottom removable gland plate and with necessary adopter boxes if any. The DB should be double door with provisioin of MCB etc. as required including cuting of wall and plastering the same with neat finish. It comprising as follows:-				
	Incomer : 32 A 2P MCB				

S.No	Description Of Work	Qty	Unit	Rate	Amount
	Outgoings:				
	16/10A SP MCBs- 10 Nos	1.00	Set		
5	Inverter DB (8WAY SPN DB)				
	8 Way SPN Distribution board with neutral bar, earth bar, cables ties,top and bottom removable gland plate and with necessary adopter boxes if any. The DB should be double door with provision of MCB etc. as required including cutting of wall and plastering the same with neat finish. It comprising as follows:-				
	Incomer : 20A DP MCB				
	Outgoings:				
	10A SP MCBs- 6 Nos	1.00	Set		
6	Supply&Installation of the following with the necessary Powder coated metal enclosure.				
	a) 25 A DP MCB for Strong Room/ Fire Alarm System	2.00	Set		
	b) 63A FP MCB-UPS I/P(Branch)	2.00	Set		
7	Supply&Installation of the following with the necessary Weather proof PVC enclosure and adapter box if necessary.				
	a) 40 A DP MCB for UPS O/P	2.00	Set		
8	Supply & Installation of 3 Pin 25A Metal Clad Socket with top in a specified company manufactured box with				
	25A DP MCB for AC to be kept in EB room	7.00	Set		
9	Supply and fixing of RYB Indicator Lamp with enclosure	1.00	Set		
10	Supply and fixing of Rotary Switch with RYB Indicator Lamp with enclosure including Point wiring from LDB, AC DB, UPS DB	1.00	Set		
B	LT CABLES				
	Supply & Laying of the following cables in built up trenches, on wall, or in the ground as per the case				
	may be, with proper clamping with necessary fixing				
	materials etc., Installing testing and commissioning of UG Cable				
11	3.5 Core X 35 Sqmm Aluminium Armored cable+ 8Swg Copper Wire (Meter to Main Panel)	28.00	Mtr		
12	4 Core X 25 Sqmm Aluminium Armored cable+ 8Swg Copper Wire (Main Panel to AC DB)	15.00	Mtr		

S.No	Description Of Work	Qty	Unit	Rate	Amount
C	End Termination of the above cables with proper Glands				
	Lugs, etc.,				
13	3.5 Core X 35 Sqmm Aluminium Armored cable	2.00	Nos		
14	4 Core X 25 Sqmm Aluminium Armored cable	2.00	Nos		
D	WIRING				
15	Light/Fan point wiring with 3 Runs of 1.5 sqmm flame 25/20MM PVC conduit with Bend, Couplings, etc., And fixing with clamps screws etc.All conduits to be laid above the false ceiling / partition / concealed in the wall etc. Wiring to be connected with supply and Fixing of 6A Modular type switch with suitable Modular plate and Metal Box (Approx True Ceiling Ht - 11'0")				
	a) One light Controlled by One Switch	30.00	Pts		
	b) Two Lights Controlled by one Switch	17.00	Pts		
	b) Three Lights Controlled by one Switch	5.00	Pts		
	d) 6A Switch box Sockets in the switch board itself	15.00	Pts		
	e) Exhaust Fan points	5.00	Pts		
	f) Ceiling fan with Step Type Regulator point	7.00	Pts		
	g)Floor Mount Pedestal Fan Point (1X5A Switch and 1X5A Sockets including inverter wiring)	10.00	Pts		
	h) Calling Bell Push with Bell (Remote will not accept)	1.00	Set		
16	Supply & Wiring with FRLS multi stranded copper wire for Circuits, Computer Points, Power points within 25/20MM FRLS PVC conduits with all necessary accessories and with proper clamps and to be concealed below the false ceiling				
	It comprises as follows:-				
	a) 2Runs of 2.5Sqmm +1Run 1.5Sq.mm FRLS multi stranded copper wire in FRLS PVC conduit (from LDB to switch box/ Sign Board)	370.00	Mtr		
	b) 2Runs of 2.5Sqmm +1Run 1.5Sq.mm FRLS multi stranded copper wire in FRLS PVC Raw Power points to be provided for cash cabin, manager cabin & alternate points in running counter (minimum 3 points in one circuit)	320.00	Mtr		
	c) 2Runs of 2.5Sqmm +1Run 1.5Sq.mmFRLS multi stranded copper wire in FRLS PVC Computer points(minimum 3 points in one circuit)	310.00	Mtr		

S.No	Description Of Work	Qty	Unit	Rate	Amount
	d) 2 Runs of 4 Sqmm copper wire + 1 R 2.5 Sqmm FRLS multistrand ed copper wire in FRLS PVC conduit - For CMS Split AC & ATM Split Acs/ ATM UPS	160	Mtr		
	e) 2 Runs of 6.0 Sqmm copper wire + 1 R 4.0 Sqmm copper wire in PVC conduit - Main Panel to LDB, RPDB and ATMS i/p/ ATM i/p	95	Mtr		
	g) 4 Runs of 6.0 Sqmm copper wire + 1 R 4.0 Sqmm Copper in PVC conduit for Main Panel to AC DB/ LDB, RPDB	22	Mtr		
	h) 4 Runs of 10.0 Sqmm copper wire + 1 R 4.0 Sqmm Copper in PVC conduit for Main Panel to AC DB	10	Mtr		
E	POWER POINT OUTLETS				
17	Supply & Installation of 3 Nos of 6A Sockets controlled by 2 Nos of 6A Switches modular type housed in a PVC box with PVC cover plates. The boxes to be fixed either in wall or partitions/ work stations below working top. UPS	10.00	Set		
18	Supply & Installation of 2 Nos of 6A Sockets controlled by 1 Nos of 6A Switch modular type housed in a PVC box with PVC cover plates. The boxes to be fixed either in wall or partitions/ work stations below working top. Raw power	10.00	Set		
19	Supply & Installation of 1 No of 16A Sockets controlled by 1 No of 16A Switch modular type housed in a single manufacturers zinc passivated PVC box with PVC cover plates. The boxes to be fixed either in wall or partitions/ work stations below working top.	15.00	Set		
20	Supply & Installation of 5 Nos of 6A Sockets controlled by 1 Nos of 16A Switches modular type housed in a MS box with PVC cover plates. The boxes to be fixed either in wall or partitions/ work stations below working top.	2.00	Set		
F	LIGHTING FIXTURES				
21	Supply, Fixing & Commissioning of 2'0"x2'0" Recess mounted 36 W LED minimum 3600 Luminaire lights with complete PMMA diffuser including Drives and on Mineral Fibre Ceiling.	25.00	Set		
22	Supply, Fixing & Commissioning of 15W high efficiency LED downlighter 1125 luminaire with flushed diffuser including necessary fixing brackets.	22.00	Set		
23	Supply, Fixing & Commissioning of 11W high efficiency LED downlight 825 luminaire with flushed diffuser including necessary fixing brackets.	6.00	Set		

S.No	Description Of Work	Qty	Unit	Rate	Amount
24	Supply, Fixing & Commissioning of Surface Mounted 4'0" - 1 x 20W LED Fittings(Batten type) with necessary accessories, etc.,	16.00	Set		
25	Supply, Fixing & Commissioning of Ceiling Mounted 9W LED Fittings with necessary accessories, etc.,	3.00	Nos		
26	Supply, Fixing & Commissioning of LED rope light of approved colour with complete set of necessary accessories, to install the cove of partition / false ceiling,. The fittings should be supported with necessary clamps. Make - Havels, Philips, wipro, Chrompton	30.00	Rmt		
27	Supply, Fixing & Commissioning of 1200mm Ceiling Fan to be fixed on existing / erected clamps with necessary down rods and with all fixing accessories etc.	7.00	Nos		
28	Supply, Fixing & Commissioning of 305mm Sweep heavy duty Exhaust fan by providing necessary cutting on walls including plastering, painting works etc if required.	4.00	Nos		
29	Supply and fixing floor Mounting fan with clamp	10.00	Nos		
G	EARTHING				
30	Providing dedicated earthing with 600 X 600 X 1mm copper plate along with 50mm dia.3 Mtr long G.I pipe with other accessories in the earth filled with necessary salt,charcoal,etc. It should be covered with G.I/ Premasoned Cement Plasteted Manhole cover with necessary civil works.etc Dedicated Earth for UPS	1.00	Set		
31	Providing general earthing with 50mm dia. 3 Mtr long G.I pipe with other accessories in the earth filled with necessary salt,charcoal,etc. It should be covered with G.I Manhole cover with necessary be covered with G.I/ Premasoned Cement Plasteted Manhole cover with necessary Civil Works, etc.,Body earth for Panels, DB	2.00	Set		
32	Supply and installation of 10 Sqmm multi strand copper wire Flame retardant PVC insulated to be drawn in 20mm dia PVC conduit and to be clamped on wall with GI clamps and terminations at both ends (For UPS earthing)	45.00	Mtr		
33	Supply and installation of 6 Sqmm multi strand copper wire Flame retardant insulated to be drawn in 20mm dia PVC conduit and to be clamped on wall with GI clamps terminations at both ends (For Body earthing)	75.00	Mtr		
H	TELE COMMUNICATION:				
34	Supply & Laying of 2pair telephone cable in the 25/20 MM PVC conduit for all telephone points	270.00	Mtr		
35	Supply & Laying of 20 pair telephone cable in the				

S.No	Description Of Work	Qty	Unit	Rate	Amount
	20MM PVC conduit for all telephone points.	220.00	Mtr		
36	Supply & Fixing of RJ 11 Telephone Sockets, Face	7.00	Set		
37	Supply & Installation of 20 Pair KRONE Box with Enclosure	1.00	Set		
I	PVC CONDUITS FOR DATA CABLING:				
38	Supply & Laying of 25mm dia PVC conduit and makinng holes in the aluminium partitions/wall Concealing, Civil Works, all accessories as required	270.00	Mtr		
39	Supply and installation zinc passivated MS box for installing RJ-45 outlts in wall/ patitions etc	20.00	No		
40	Supply and installation cat 6 cable	280	Mtr		
41	9U wall mount rack complete with accessories and power tray	1	No		
	Patch Card				
42	1mtr	18.00	Nos		
43	2Mtr	18.00	Nos		
	ELECTRICAL WORKS TOTAL::EXCLUDING GST 18%				
	ELECTRICAL WORKS TOTAL::INCLUDING GST 18%				